

ADDENDUM # 6

REQUEST FOR PROPOSALS FOR THE ARNEILL RANCH PARK RENOVATION PROJECT SPECIFICATION NO. 21-03

DATE: June 7, 2021

ISSUED BY: PLEASANT VALLEY RECREATION AND PARK DISTRICT

1605 East Burnley St. Camarillo, Ca. 93010

(805)-482-5396 Phone; (805)482-7591 Fax

PROJECT: REQUEST FOR PROPOSALS FOR THE ARNEILL RANCH PARK RENOVATION PROJECT SPECIFICATION NO. 21-03

ISSUED to: For Distribution to Bid Proposers _____

This Addendum forms a part of the Contract Documents and modifies the original Contract Documents as noted below.

This Addendum consists of THREE (3) pages and the modifications to the document noted below. CLARIFICATION OF BID DOCCUMENT (Submittals).

Please add this to you bid sheet.

1002 STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

1002-1 SCOPE

1002-1.1 The Contractor shall provide a Storm Water Pollution Prevention Plan (SWPPP) for construction activities that disturb one acre or more, that describes in specific detail the Contractor's program to prevent contamination of the storm water collection system. For construction activities that disturb less than one acre, Contractor shall prepare and submit the County of Ventura Storm Quality Management Program (SW-1) form. The program shall address both common construction activities and extraordinary events.

1002-1.2 The SWPPP shall comply with the State Water Board Construction General Permit. The SWPPP shall address prevention of particulate matter from entering the storm water system whether from routing operations or due to spills. The SWPPP must address practices for reducing the introduction of particulates or pollutants on the jobsite (prevention) and the containment, collection and disposal of particulates or pollutants that occur on the jobsite.

1002-1.3 The Contractor is responsible for all aspects of the SWPPP/SW-1. The City Inspector or Engineer will issue a stop notice for any failure to meet or maintain the Project site within the approved SWPPP.

1002-2 CONSTRUCTION

The Contractor shall provide continuously at the jobsite all of the tools, equipment, and materials necessary to implement the SWPPP/SW-1 at all times from Project initiation through completion, including any punch list or warranty work on the Project.

- a. The Contractor shall submit 3 copies of the SWPPP a minimum of ten (10) Working Days prior to beginning construction. **Construction shall not begin until the SWPPP/SW-1 is approved by the City Engineer.**
- b. Protection of Existing Storm Water System:
The Contractor shall protect the existing storm water system for entrance of particulates and pollutants. Such protection shall include implementing the BMPs as outlined in the SWPPP.
In addition to the BMPs outlined in the Ventura County Stormwater Quality Management Plan, the protection system shall have a minimum of three features:
 - 1) A particulate filter of Geosynthetics material securely fastened in place such that it cannot be bypassed without significant physical damage,
 - 2) A prefilter for the particulate filter, and
 - 3) On-hand materials to close off the inlet or opening in the case of a significant pollution spill.
- c. Materials Storage Areas:
All storage areas where liquid construction materials such as asphalt emulsions, paving oils, and seal coat materials are held shall be protected by a physical barrier capable of containing the entire volume of stored liquid materials. During active construction activities, portions of the barrier may be removed for access. However, the barrier materials must be readily accessible for replacement by on-site construction personnel. The barrier must be in place at all times during the absence of Contractor personnel at the storage site.
- d. System Inspection and Maintenance:
The Contractor shall inspect and repair or replace any damaged or clogged element on a daily basis. During periods of precipitation where any runoff occurs, Contractor must check the system twice a day, seven days a week, whether or not any Work has been performed. The daily checks shall be between 6 to 9 AM and 4 to 8 PM.
The Contractor shall provide a monitoring log of each inspection.
- e. Non-Storm Spills or Pollution:
The SWPPP shall address practices for cleanup of spilled or leaked pollutants such as hydraulic oil from damaged or leaking equipment. The SWPPP shall include readily available equipment and materials to contain and absorb the pollutants, collection of these materials, and disposal of

the materials to an approved disposal site. The SWPPP shall include ultimate disposal from the Contractor's yard.

The Contractor shall keep a record of any spills on the daily inspection logs. In addition, at the end of the Project upon acceptance by the Project Manager, the Contractor must certify that all contaminated materials have been properly disposed in accordance with the SWPPP.

1002-3 MEASUREMENT AND PAYMENT

The Contractor shall be paid for the Work of preparing, implementing, inspecting, maintaining, and removing the SWPPP on a lump sum basis as enumerated in the Bid Sheets. In addition, failure to perform and document the required daily inspections shall result in a penalty of \$250 per Calendar Day. The imposition of the penalty shall not relieve the Contractor of any obligations of these Project requirements.

Payment for the Work involved under the bid item for the SWPPP may be made on a partial payment system based on the completion of the following stages of the Work:

<u>Work Description</u>	<u>Payment</u>
Develop Plan	10% of Bid amount
Initial Plan Implementation	10% of Bid amount
Removal of BMPs at Completion	10% of Bid amount
Inspection and Maintenance of SWPPP	70% of Bid amount